

- 2. INSTALLED TANGENT TO LENGTH OF NEED OR WITH A TAPER OF 25:1 OR LESS.
- 3. WOOD OR STEEL BREAKAWAY POSTS MAY BE USED FOR THIS SYSTEM.
- 4. NCHRP 350 TEST LEVEL 3 (50'-0" LONG) SYSTEM IS SHOWN. A REDUCED SPEED TEST LEVEL 2 (25'-0" LONG) SYSTEM IS ALSO AVAILABLE.